

Before Starting Installation



**Warning**

Shut power to unit prior to any work being done. Personal injury or death could result.

Only qualified HVAC service personnel should install, troubleshoot, repair or service HVAC and related HVAC equipment.




ILL. 1




# III.2 Control Wiring Diagram

## MIXING BOX DRY BULB CONTROL WIRING DIAGRAM GAS ELECTRIC




MIXING BOX  
ENTHALPY CONTROL WIRING DIAGRAM  
GAS ELECTRIC



ILL. 3  
Control Wiring Diagram



MIXING BOX  
ENTHALPY CONTROL WIRING DIAGRAM  
HEAT PUMP



ILL. 5  
Control Wiring Diagram

**Table 1: Economizer Controller Terminations**

| Board Name <sup>1</sup>        | Description                    | Type                | Termination Type        |
|--------------------------------|--------------------------------|---------------------|-------------------------|
| <b>Analog Inputs (AIs)</b>     |                                |                     |                         |
| SAT                            | Supply Air Temperature, C      | Resistive           | Spade                   |
| RAT                            | Return Air Temperature, C      | Resistive           | Spade                   |
| OAT                            | Outdoor Air Temperature, C     | Resistive           | Spade                   |
| OAH                            | Outdoor Air Humidity, R, C     | 0 to 10 V           | Spade                   |
| RAH                            | Return Air Humidity, R, C      | 0 to 10 V           | Spade                   |
| IAQ                            | Indoor Air Quality Input, R, C | 0 to 10 V           | Pin Connector           |
| BPS*                           | Bldg Pressure Input, R, C      | 0 to 10 V           | Spade                   |
| OAF*                           | Outdoor Air Flow, R, C         | 0 to 10 V           | Pin Connector           |
| OAQ*                           | Outdoor Air Quality, R, C      | 0 to 10 V           | Pin Connector           |
| DFB                            | Damper Feedback Position, C    | 0 to 10 V           | Pin Connector           |
| <b>Analog Outputs (AOs)</b>    |                                |                     |                         |
| DMP                            | Damper Output                  | 0 to 10 V           | Pin Connector           |
| PE VFD*                        | PE VFD Output, C               | 0 to 10 V           | Spade                   |
| <b>Binary Inputs (BIs)</b>     |                                |                     |                         |
| Y1O                            | Y1 Status                      | 24 VAC              | Pin Connector           |
| Y2O                            | Y2 Status                      | 24 VAC              | Pin Connector           |
| W1                             | W1 Status or O/B Status        | 24 VAC              | Pin Connector           |
| SD                             | Shutdown Status                | 24 VAC              | Pin Connector           |
| PRG*                           | Purge Status                   | 24 VAC              | Pin Connector           |
| OCC                            | OCC Status                     | 24 VAC              | Pin Connector           |
| <b>Binary Outputs (BOs)</b>    |                                |                     |                         |
| ALM                            | Alarm Output, Output COM       | Relay (dry contact) | Spade                   |
| Y1O                            | Y1 Output                      | Relay (24 VAC)      | Pin Connector           |
| Y2O                            | Y2 Output                      | Relay (24 VAC)      | Pin Connector           |
| ERV-EXH                        | Exhaust Fan/ERV Output         | Relay (24 VAC)      | Pin Connector           |
| <b>Additional Terminations</b> |                                |                     |                         |
| R                              | R (24 VAC Class 2 Supply)      | 24 VAC              | Spade                   |
| <b>Board Name<sup>1</sup></b>  | <b>Description</b>             | <b>Type</b>         | <b>Termination Type</b> |
| C                              | C (24 VAC Class 2 Common)      | 24 VAC              | Spade                   |
| SA Bus*                        | SA Bus                         | RS-485 Comm         | Spade                   |

1. The \* denotes the Inputs and Outputs (I/Os) are only on the Advanced model.

## Accessories

**Table 2: Accessories**

| Product Code Number | Description                                |
|---------------------|--|
| TE-636GV-2          | Temperature Sensor                         |
| HE-6862-0N00WS      | Temperature/Humidity Sensor                |
| M9205-GGA-YK10      | Damper Actuator                            |
| CD-W00-x0-1         | Space CO <sub>2</sub> Sensor (recommended) |
| CD-Pxx-00-0         | Duct CO <sub>2</sub> Sensor (recommended)  |
| RK-WRH1001-0        | Wiring Harness                             |

**Note:** For Outdoor Air (OA) Flow monitoring consult your local Johnson Controls branch or RRS representative to determine the best product to use for your application. Due to the various sensors available for monitoring OA flow, we cannot recommend one specific product.

Table 3: Economizer controller terminations

| Name                 | Description  | Type                                   | Termination Type |
|----------------------|--|--|------------------|
| Analog Inputs (AIs)  |  |  |                  |
| SAT                  | Supply Air Temperature, C<br>Sensor product code: TE-636GV-2       | Resistive                              | Spade            |
| RAT                  | Return Air Temperature, C<br>Sensor product code: HE-69630NS-2     | Resistive                              | Spade            |
| OAT                  | Outdoor Air Temperature, C<br>Sensor product code: HE-69630NS-2    | Resistive                              | Spade            |
| OAH                  | Outdoor Air Humidity, R, C<br>Sensor product code: HE-69630NS-2    | 0 VDC to 10 VDC                        | Spade            |
| RAH                  | Return Air Humidity, R, C<br>Sensor product code: HE-69630NS-2     | 0 VDC to 10 VDC                        | Spade            |
| IAQ                  | Indoor Air Quality Input, R, C<br>Sensor product code: CD-W00-00-2 | 0 VDC to 10 VDC                        | Pin Connector    |
| BPS                  | Building Pressure Input, R, C                                      | 0 VDC to 10 VDC                        | Spade            |
| OAF                  | Outdoor Air Flow, R, C   | 0 VDC to 10 VDC                        | Pin Connector    |
| OAQ                  | Outdoor Air Quality, R, C<br>Sensor product code: CD-P1000-00-00   | 0 VDC to 10 VDC                        | Pin Connector    |
| DFB                  | Damper Feedback Position, C  | 0 VDC to 10 VDC, or<br>2 VDC to 10 VDC | Pin Connector    |
| Analog Outputs (AOs) |  |  |                  |
| DMP                  | Damper Output<br>Damper actuator product code:<br>M9205-GGA-EC01   | 0 VDC to 10 VDC, or<br>2 VDC to 10 VDC | Pin Connector    |
| PE VFD               | PE VFD Output, C   | 0 VDC to 10 VDC                        | Spade            |

**Table 3: Economizer controller terminations**

| Name                           | Description               | Type                | Termination Type        |
|--------------------------------|---------------------------|---------------------|-------------------------|
| <b>Binary Inputs (BIs)</b>     |                           |                     |                         |
| Y1                             | Y1 Status                 | 24 VAC              | Pin Connector           |
| Y2                             | Y2 Status                 | 24 VAC              | Pin Connector           |
| W1                             | W1 Status or O/B Status   | 24 VAC              | Pin Connector           |
| SD                             | Shutdown Status           | 24 VAC              | Pin Connector           |
| PRG                            | Purge Status              | 24 VAC              | Pin Connector           |
| OCC                            | OCC Status                | 24 VAC              | Pin Connector           |
| <b>Binary Outputs (BOs)</b>    |                           |                     |                         |
| ALM                            | Alarm Output, Alarm COM   | Relay (dry contact) | Spade                   |
| Y1O                            | Cooling Stage 1           | Relay (24 VAC)      | Pin Connector           |
| Y2O                            | Cooling Stage 2           | Relay (24 VAC)      | Pin Connector           |
| ERV-EXH                        | Exhaust Fan/ERV Output    | Relay (24 VAC)      | Pin Connector           |
| <b>Additional Terminations</b> |                           |                     |                         |
| R                              | R (24 VAC Class 2 Supply) | 24 VAC              | Spade and Pin Connector |
| C                              | C (24 VAC Class 2 Common) | 24 VAC              | Spade and Pin Connector |
| SA Bus                         | SA Bus                    | RS-485 Comm         | Spade                   |

## Accessories

**Table 4: Accessories**

| Product code number | Description   |
|---------------------|---|
| TE-636GV-2          | Duct temperature sensor   |
| HE-69630NS-2        | Temperature and humidity sensor   |
| TE-6363P-1          | Outside air temperature sensor  |
| M9205-GGA-EC01      | Damper actuator   |
| CD-W00-00-2         | Space CO <sub>2</sub> sensor<br><i>ⓘ</i> <b>Note:</b> It is best practice to install this sensor. |
| CD-P1000-00-00      | Duct CO <sub>2</sub> sensor   |
| RK-WRH1001-0        | Wiring harness  |
| NSB8BTN241-0        | Zone temperature sensor with fault code display capability, no logo, white                        |
| NSB8BTN243-0        | Zone temperature sensor with fault code display capability, no logo, black                        |

## Powering the unit

When you apply 24 VAC power to the C and R terminals (on the upper right side of the unit), the controller begins a start-up sequence.



During the start-up sequence, the LCD displays a start-up text and a countdown. The buttons are **not** functional. The following table shows the status of the LEDs during the start-up sequence.

**Table 5: LED status during start-up**

| LED            | Status  |
|----------------|---|
| Power (green)  | On steady if the C and R terminals receive power  |
| Fault (red)    | Blink   |
| SA Bus (green) | For approximately 10 seconds: On steady<br><br>After approximately 10 seconds: <ul style="list-style-type: none"> <li>• Blink: Normal communication</li> <li>• On steady: Communication lost</li> </ul> |

After the start-up sequence finishes, the display is blank on both lines if no alarm is active. The red Fault LED turns off.

## Menu structure

The following section describes the menus and submenus for the RRS Economizer controller. The Level 1 menus are the following:

- Setup
- Status
- Advanced Setup
- Advanced Status
- Controller
- Update
- Self Test
- View Results


Each menu and the submenus are detailed below.

- ⓘ **Note:** The parameters that appear in your menu are based on the equipment configuration. See Table 16 for a list of the conditions that determine whether a menu item is visible.

## Understanding the local LCD

After you apply power to your rooftop unit (RTU), a start-up countdown begins on the Economizer LCD. When the controller is ready, the screen is blank to indicate that no faults are present. Use the push buttons next to the LCD to navigate through the menus.

**Figure 10: LCD and buttons on the Economizer**



Each menu item is either a submenu or a property. To move the cursor, press the up and down arrow buttons. To select an item, press the right arrow button. To go back to the previous item, press the left arrow button.

To modify the value of a property, press the right arrow button to select the property, and then press the up and down arrow buttons to select a new value.

## Setup menu

**Table 6: Setup menu**

| Level 2 on MAP Gateway (on LCD)  | Default values    | Available values  |
|--|-------------------|---|
| Language   | English           | English, French, Spanish                                  |
| Install Month  | 1                 | 1 to 12   |
| Install Day  | 1                 | 1 to 31   |
| Install Year   | 2019              | 2015 to 2030  |
| Units  | IP                | IP, SI  |
| Equipment Type   | Conv RTU          | Conv RTU, Heat Pump                                       |
| Thermostat Type  | W                 | W, B, O   |
| Number of Cooling Stages Installed (Comp Stages)                                     | 1                 | 1 to 2  |
| Fan Control Type   | Single Speed      | Single Speed, Two Speed                                   |
| Dry Bulb Setpoint (Dry Bulb Stpt)  | 68°F              | 35°F to 86°F  |
| Economizer Outdoor Air Enthalpy Setpoint (OA Enth Setpt)                             | 27 BTU/lb Dry Air | 10 BTU/lb to 50 BTU/lb Dry Air                            |
| Economizer Minimum Position Setpoint (Damper Min Pos)                                | 10%               | 0% to 100%  |
| Economizer Damper Minimum Position Low Speed Fan (Low Spd Min Pos)                   | 45%               | 0% to 100%  |
| Exhaust Setup  | None              | None, Non-modulating Control, Variable Frequency Fan, ERV |
| Economizer Damper Position for Exhaust Fan to Turn On (Damper % Fan On)              | 60%               | 0% to 100%  |
| Economizer Damper Position for Exhaust Fan to Turn Off (Damper % Fan Off)            | 20%               | 0% to 100%  |
| Damper Position for Exhaust Fan to Turn Off Low Speed Fan (Damper % Fan Off Lo Spd)  | 40%               | 0% to 100%  |
| Damper Position for Exhaust Fan to Turn On Low Speed Fan (Damper % Fan On Lo Spd)    | 80%               | 0% to 100%  |
| Damper Position for Exhaust Fan to Turn Off High Speed Fan (Damper % Fan Off Hi Spd) | 20%               | 0% to 100%  |
| Damper Position for Exhaust Fan to Turn On High Speed Fan (Damper % Fan On Hi Spd)   | 60%               | 0% to 100%  |
| Demand Ventilation Mode of Operation (Vent Mode)                                     | Disabled          | Disabled, Controlled by IAQ, Diff between IAQ and OAQ     |
| Demand Ventilation Indoor Air Quality Setpoint (Vent IAQ Stpt)                       | 1000 ppm          | 0 ppm to 2000 ppm   |
| Relearn System<br>Relearns the sensors connected to the controller.                  | False             | True, False   |

## Status menu

**Table 7: Status menu**

| Level 2 on MAP Gateway (on LCD)              | Description   |
|--|---|
| Unit Status                                  | Displays the overall status of the unit                               |
| Economizer Status (Econ Status)              | Displays the status of the Economizer damper control                  |
| Econ Free Cooling Available (Free Clg Avail) | Displays whether free cooling is available. Possible values: Yes, No. |
| Economizer Damper % Command (Damper Command) | Displays the damper command percentage. Default value: 15%.           |

**Table 7: Status menu**

| Level 2 on MAP Gateway (on LCD)              | Description  |
|--|--|
| Economizer Damper Position (Damper Feedback) | Displays the percentage reading from the damper feedback sensor.                         |
| Supply Air Temperature (Supply Temp)         | Displays the reading from the SAT sensor, in the range of -40°F to 150°F.                |
| Outdoor Air Temperature (Outdoor Temp)       | Displays the reading from the OAT sensor, in the range of -40°F to 140°F.                |
| Outdoor Humidity                             | Displays the percentage reading from the OAH sensor in the range of 5% to 100%.          |
| Outdoor Air Enthalpy                         | Displays the OA enthalpy.  |
| Return Air Temperature (Return Temp)         | Displays the reading from the RAT sensor, in the range of 0°F to 140°F.                  |
| Return Air Humidity (Return Humidity)        | Displays the percentage reading from the RAH sensor, in the range of 5% to 100%.         |
| Return Air Enthalpy                          | Displays the RA enthalpy.  |
| Occupancy                                    | Displays the reading from the occupancy sensor. Possible values: Occupied, Unoccupied.   |
| Comp Status                                  | Displays the overall compressor status.  |
| Compressor Stage 1 Command (Compressor 1)    | Displays the compressor stage 1 command.   |
| Compressor Stage 2 Command (Compressor 2)    | Displays the compressor stage 2 command.   |
| Y1-Thermostat (Y1-Tstat)                     | Displays the thermostat Y1 status.   |
| Y2-Thermostat (Y2-Tstat)                     | Displays the thermostat Y2 status.   |
| W1-Thermostat (W1-Tstat)                     | Displays the thermostat W1 status.   |
| Exhaust Fan Status (Exhaust Status)          | Displays the exhaust fan status.   |
| ERV Status                                   | Displays the ERV status.   |
| Exhaust Fan Command (Exhaust Fan)            | Displays the exhaust fan command. Possible values: Off, On.                              |
| Exhaust Fan VFD % Command (Exhaust Command)  | Displays the exhaust fan VFD command percentage.   |
| Building Static Pressure (Bldg Pressure)     | Displays the reading from the BSP sensor in the range of -0.25 in. W.C. to 0.25 in. W.C. |

## Advanced Setup menu

**Table 8: Advanced Setup menu**

| Level 2 on MAP Gateway (on LCD)                               | Default values | Available values                               |
|---|----------------|--|
| Economizer Enabled for Operation (Econ Enable)                | Yes            | Yes, No  |
| Supply Temp Stpt  | 55°F           | 38°F to 70°F                                   |
| Damper Min Value  | 2 VDC          | 0 VDC to 2 VDC                                 |
| Feedback Min Value  | 2 VDC          | 0 VDC to 2 VDC                                 |
| Free Cooling Selection (Free Clg Select)                      | Auto           | Dry Bulb, Single Enthalpy, Dual Enthalpy, Auto |
| Fault Detection Enable (Fault Detect En)                      | Enable         | Enable, Disable                                |
| Low Ambient Enabled (Lo Ambient En)                           | Yes            | Yes, No  |
| Low Ambient Economizer Setpoint (Lo Ambient Stpt)             | 32°F           | 0°F to 60°F                                    |
| Low Ambient Economizer Minimum Position (Lo Amb Min Pos)      | 0%             | 0% to 80%                                      |
| OAT Cooling Cutout Enabled (ClgOATCutout-En)                  | No             | Yes, No  |
| OAT Cooling Cutout (ClgOATCutout)                             | 45°F           | -45°F to 80°F                                  |
| Excessive SAT Setpoint (Excess SAT Stpt)                      | 44°F           | 35°F to 135°F                                  |
| High Limit Shutoff (High OA Shutoff)                          | 75°F           | 0°F to 86°F                                    |
| Demand Ventilation Maximum Economizer Position (Vent Max Pos) | 50%            | 0% to 100%                                     |
| DCV Econ Dmpr Min Pos Hi Spd Fan (Vent Min Pos Hi)            | 20%            | 0% to 100%                                     |
| DCV Econ Dmpr Min Pos Lo Spd Fan (Vent Min Pos Lo)            | 50%            | 0% to 100%                                     |
| Building Pressure Setpoint (Bldg Press Stpt)                  | 0.1 in. W.C.   | -0.25 in. W.C. to 0.25 in. W.C.                |
| Fresh Air Intake Enable (Fresh Air Enable)                    | Off            | On, Off  |

**Table 8: Advanced Setup menu**

| Level 2 on MAP Gateway (on LCD)            | Default values | Available values    |
|--|----------------|---------------------|
| Fresh Air Intake Setpoint (Fresh Air Stpt) | 800 cfm        | 0 cfm to 10,000 cfm |
| Compressor Min Off Time (Cmp Min Off Time) | 60 s           | 60 s to 600 s       |
| Compressor Min On Time (Cmp Min On Time)   | 60 s           | 60 s to 600 s       |
| Compressor 1 Lockout (Comp 1 Lockout)      | Normal         | Normal, Lockout     |
| Compressor 2 Lockout (Comp 2 Lockout)      | Normal         | Normal, Lockout     |
| Compressor Stage Enabled (Comp Enable)     | Yes            | Yes, No             |
| Altitude                                   | 0 ft           | 0 ft to 15,000 ft   |

## Advanced Status menu

**Table 9: Advanced Status menu**

| Level 2 on MAP Gateway (on LCD)                          | Description   |
|--|---|
| Indoor Air Quality (Indoor Quality)                      | Displays the reading from the indoor air quality sensor in the range of 250 ppm to 2,000 ppm. |
| Outdoor Quality  | Displays the reading from the outdoor air quality sensor.                                     |
| Fresh Air Intake Value (Fresh Air Flow)                  | Displays the reading from the outdoor air flow sensor.  |
| Purge  | Displays the purge status. Possible values: Normal, Alarm.                                    |
| Shutdown   | Displays the shutdown status. Possible values: On, Off.                                       |
| OA Damper Control State (Damper State)                   | Displays the current damper state.  |
| Compressor Control Mode (Comp Ctrl Mode)                 | Displays the compressor control mode.   |
| Exhaust Control State (Exhaust State)                    | Displays the exhaust state.   |
| Demand Ventilation Status (Vent Status)                  | Displays the demand ventilation status.   |
| Comp Avail State   | Displays the compressor availability.   |
| Compressor Stage 1 Status (Comp 1 Status)                | Displays the status of compressor 1.  |
| Compressor Stage 2 Status (Comp 2 Status)                | Displays the status of compressor 2.  |
| Econ Fault State   | Displays the economizer fault state.  |
| Excess SAT State   | Displays information on the excess SAT state.   |
| Exhaust Control Determination State (Exh Det State)      | Displays the exhaust detection state.   |
| Exhaust Control Mode (Exhaust Mode)                      | Displays the current exhaust mode.  |
| Fresh Air Intake Control Active (Fresh Air Active)       | Displays the fresh air active state.  |
| Mechanical Thermostat Sequencer State (Mech Tstat State) | Displays the status of the mechanical thermostat.   |
| OA Damper Control Mode (Damper Mode)                     | Displays the damper mode.   |
| Staged Output Control State (Staged Out State)           | Displays the state of the staged output control.  |
| Startup Delay State (Strt Delay State)                   | Displays the start-up delay state.  |

## Controller menu

**Table 10: Calibration submenu**

| Level 3 on MAP Gateway (on LCD) | Default values | Available values                |
|---------------------------------|----------------|---------------------------------|
| SAT Offset                      | 0°F            | -5°F to 5°F                     |
| OAT Offset                      | 0°F            | -5°F to 5°F                     |
| OAH Offset                      | 0%             | -5% to 5%                       |
| RAT Offset                      | 0°F            | -5°F to 5°F                     |
| RAH Offset                      | 0%             | -5% to 5%                       |
| BSP Offset                      | 0 in. W.C.     | -0.05 in. W.C. to 0.05 in. W.C. |
| IAQ Offset                      | 0 ppm          | -100 ppm to 100 ppm             |
| OAQ Offset                      | 0 ppm          | -100 ppm to 100 ppm             |
| FAI Offset                      | 0 cfm          | -100 cfm to 100 cfm             |
| Fresh Air Range                 | 10,000 cfm     | 0 cfm to 50,000 cfm             |

**Table 11: Misc submenu**

| Level 3 on MAP Gateway (on LCD)        | Default values | Available values |
|--|----------------|------------------|
| Comp 1 Runtime                         | 0 minutes      | 10,000 minutes   |
| Comp 2 Runtime                         | 0 minutes      | 10,000 minutes   |
| Reset Accumulator                      | No             | Yes, No          |
| PID Tuning Reset                       | False          | True, False      |
| Damper Integral Time (Damper Int Time) | 0              | N/A (read-only)  |
| Damper Prop Band                       | 0              | N/A (read-only)  |
| Exhaust Integral time (Exh Int Time)   | 0              | N/A (read-only)  |
| Exhaust Prop Band (Exh Prop Band)      | 0              | N/A (read-only)  |

**Table 12: Controller Information submenu**

| Level 2            | Description  | Available values   |
|--------------------|--|--|
| Brightness Setting | You can set the brightness of the display.<br>Default value: 5         | 3 to 10  |
| Firmware Version   | Displays the current firmware version.                                 | N/A  |
| Firmware Status    | Displays the firmware status.  | Firmware Versions OK<br>Firmware Versions Do Not Match the Package |
| Language           | You can set the language of the device.<br>Default value: English      | English, French, Spanish   |
| Units              | You can set the units that the device uses.<br>Default value: IP       | IP, SI   |
| Relearn System     | Relearns the sensors connected to the controller. Default value: False | True, False  |

## Update menu

**Table 13: Update menu**

| Level 2        | Description                                       | Available values                                   |
|----------------|---|--|
| View Version   | Displays the current firmware version and status. | N/A  |
| Load Firmware  | Displays a list of choices that you can load.     | N/A  |
| Backup         | You can create a backup of the device.            | Backup: Wait, Backup 0%<br>Backup: Ok, Backup 100% |
| Restore        | You can restore data from a backup file.          | BackupConfig (file name to be restored)            |
| Export Trend   | You can export trends.                            | Exporting, Export Done                             |
| SelftestReport | You can create a self-test report.                | N/A  |

## Self Test menu

**Table 14: Self Test menu**

| Level 2          | Level 3  | Level 4 | Description  |
|------------------|--|---------|--|
| Self Test Status | Current State Status<br>Self Test Status<br>Self Test Time Remaining<br>Self Test Prompt | N/A     | Displays information about the test progress or any prompts that you need to answer. |

**Table 14: Self Test menu**

| Level 2          | Level 3         | Level 4   | Description                  |
|------------------|-----------------|---|------------------------------|
| Self Test Start  | All Test        | N/A   | Runs all the tests.          |
|                  | Equipment Test  | Alarm<br>Damper<br>Compressor 1<br>Compressor 2<br>Power Exhaust<br>ERV<br>Power Ex VFD | Runs the selected test.      |
|                  | Acceptance Test | OA Ventilation<br>RTU Test<br>Economizer<br>Demand Ctl Vent<br>FDD                      |                              |
| Self Test Pause  | N/A             | N/A   | Pauses the test.             |
| Self Test Cancel | N/A             | N/A   | Cancels the test.            |
| Self Test Reset  | N/A             | N/A   | Resets the self test status. |

## View Results menu

**Table 15: View Results menu**

| Level 2   | Available values  |
|---|---|
| Alarm<br>Damper<br>Compressor 1<br>Compressor 2<br>Power Exhaust<br>ERV<br>Power Ex VFD<br>OA Ventilation<br>RTU Test<br>Economizer<br>Demand Ctl Vent<br>FDD | Stabilize, Wait, Check, Available, Not Run, Pass, Fail, Warning |

## Menu conditions

**Table 16: Menu conditional variables**

| Menu item  | Condition to appear in the menu   |
|--|---|
| <b>Exhaust Setup</b>                               | Always appears  |
| <b>Damper Position for Exhaust Fan to Turn On</b>  | Exhaust Setup set to Non-Modulating Control <b>and</b> Supply Fan Setup set to Single Speed |
| <b>Damper Position for Exhaust Fan to Turn Off</b> | Exhaust Setup set to Non-Modulating Control <b>and</b> Supply Fan Setup set to Single Speed |
| <b>Building Static Pressure Setpoint</b>           | Exhaust Setup set to Variable Frequency Fan   |
| <b>OAT Cooling Cutout Enabled</b>                  | Equipment Type set to Conv RTU  |
| <b>OAT Cooling Cutout</b>                          | Equipment Type set to Conv RTU <b>and</b> OAT Cooling Cutout Enabled set to True            |
| <b>Supply Fan Type</b>                             | Equipment Type set to Conv RTU  |
| <b>Low Ambient Economizer Setpoint</b>             | Damper Low Ambient set to Enabled   |

**Table 16: Menu conditional variables**

| <b>Menu item</b>  | <b>Condition to appear in the menu</b>  |
|---|---|
| <b>Low Ambient Economizer Minimum Position</b>                    | Damper Low Ambient set to Enabled   |
| <b>Economizer Damper Minimum Position Low Speed Fan</b>           | Supply Fan Type set to Two Speed <b>and</b> DCV set to Disabled                                   |
| <b>Demand Ventilation Maximum Economizer Position</b>             | DCV is not Disabled   |
| <b>Demand Ventilation Indoor Air Quality Setpoint</b>             | DCV is not Disabled   |
| <b>Fresh Air Intake Setpoint</b>                                  | Fresh Air Intake is Enabled   |
| <b>DCV Economizer Damper Minimum Position Low Speed Fan</b>       | Supply Fan Type set to Two Speed <b>and</b> DCV is not Disabled                                   |
| <b>DCV Economizer Damper Minimum Position High Speed Fan</b>      | Supply Fan Type set to Two-Speed <b>and</b> DCV is not Disabled                                   |
| <b>Damper Position for Exhaust Fan to Turn Off Low Speed Fan</b>  | Exhaust Setup set to Non-Modulating Control <b>and</b> Supply Fan setup is not Single Speed       |
| <b>Damper Position for Exhaust Fan to Turn On Low Speed Fan</b>   | Exhaust Setup set to Non-Modulating Control <b>and</b> Supply Fan setup is not Single Speed       |
| <b>Compressor 2 Lockout</b>                                       | The number of compressors > 1   |
| <b>Compressor 2 Test</b>  | The number of compressors > 1   |
| <b>Power Exhaust Test</b>   | Power Exhaust Test set to Non-Modulating Control  |
| <b>ERV Pivot Test</b>   | Exhaust Setup set to ERV  |
| <b>Exhaust VFD Test</b>   | Exhaust Setup set to Variable Frequency Fan   |
| <b>OA Vent Test</b>   | Fresh Air Intake is Enabled   |
| <b>DCV Test</b>   | DCV is not Disabled   |
| <b>SAT Offset</b>   | SAT Sensor connected  |
| <b>RAT Offset</b>   | RAT Sensor connected  |
| <b>OAT Offset</b>   | OAT Sensor connected  |
| <b>OAH Offset</b>   | OAH Sensor connected  |
| <b>RAH Offset</b>   | RAH Sensor connected  |
| <b>IAQ Offset</b>   | IAQ Sensor connected  |
| <b>BSP Offset</b>   | BSP Sensor connected  |
| <b>FAI Offset</b>   | FAI Sensor connected  |
| <b>OAQ Offset</b>   | OAQ Sensor connected  |
| <b>Fresh Air Range</b>  | Fresh Air Intake is Enabled   |
| <b>Damper Position For Exhaust Fan to Turn Off High Speed Fan</b> | Exhaust Setup set to Non-Modulating Control <b>and</b> Supply Fan setup is not Single Speed       |
| <b>Damper Position for Exhaust Fan to Turn On High Speed Fan</b>  | Exhaust Setup set to Non-Modulating Control <b>and</b> Supply Fan setup is not Single Speed       |
| <b>Exhaust Fan VFD Percent Command</b>                            | Exhaust Setup set to Variable Frequency Fan   |
| <b>Compressor Stage 2 Command</b>                                 | The number of compressors > 1   |
| <b>Exhaust Fan Command</b>  | Exhaust Setup not equal to None   |
| <b>Exhaust Control Determination State</b>                        | Exhaust Setup not equal to None   |
| <b>Exhaust Control Mode</b>                                       | Exhaust Setup not equal to None   |
| <b>Exhaust Control State</b>                                      | Exhaust Setup not equal to None   |
| <b>Demand Ventilation Status</b>                                  | DCV not equal to Disabled   |
| <b>Fresh Air Intake Control Active</b>                            | Fresh Air Intake is Enabled   |
| <b>Compressor Stage 2 Status</b>                                  | The number of compressors > 1   |
| <b>Exhaust Fan Status</b>   | Exhaust Setup set to Non-Modulating Control <b>or</b> Exhaust Setup set to Variable Frequency Fan |
| <b>ERV Status</b>   | Exhaust Setup set to ERV  |
| <b>Exhaust Prop Band</b>  | Exhaust Setup set to Variable Frequency Fan   |
| <b>Exhaust Integral Time</b>                                      | Exhaust Setup set to Variable Frequency Fan   |
| <b>Compressor 2 Test Status</b>                                   | The number of compressors > 1   |
| <b>Power Exhaust Test Status</b>                                  | Exhaust Setup set to Non-Modulating Control   |
| <b>ERV Pivot Test Status</b>                                      | Exhaust Setup set to ERV  |
| <b>Exhaust VFD Test Status</b>                                    | Exhaust Setup set to Variable Frequency Fan   |
| <b>OA Vent Test Status</b>  | Fresh Air Intake is Enabled   |

**Table 16: Menu conditional variables**

| Menu item       | Condition to appear in the menu |
|-----------------|---------------------------------|
| DCV Test Status | DCV is not Disabled             |
| C2 Runtime      | The number of compressors > 1   |

## Self test

### About this task:

You can perform a self test to ensure proper operation. The self test verifies configuration, inputs, outputs, and makes it possible for you to run an Acceptance Test for Title 24 compliance. You can select which specific test you would like to run for troubleshooting.

The self test has a stabilization period to drive all the outputs to OFF or 0%. The active period energizes the equipment. The VFD or Supply Fan may run throughout both the stabilization and active periods.

To begin a self test, perform the following steps:

1. Navigate to **Self-Test > Self-Test Start**.
2. Select one of the following options:
  - **All Test:** You can run all the tests.
  - **Equipment Test:** You can run one of the equipment tests, see [Equipment test](#).
  - **Acceptance Test:** You can run one of the acceptance tests, see [Acceptance test](#).

## Equipment test

For a list of the possible outputs, see Table 3. For the expected output states of the equipment test, see Table 17.

### Damper test

This test changes the damper command to 100%. The test passes if the damper feedback signal reaches 100% within three minutes. If the signal never reaches 100% within three minutes, the test fails. If there is less than 2% of damper feedback after 20 seconds, there is a warning to check the damper position feedback.

### Alarm test

This test issues an alarm to a specific output and prompts you to continue. If you continue and then confirm that the alarm is active, the test passes. If you do not respond within 10 minutes to either of the prompt messages, or you do not confirm that the alarm is active, the test fails.

### Compressor test

The compressor tests 1 and 2 are available when the occupancy binary input is in the **Occupied** state. The output (Y1 or Y2) activates, and turns on the compressor. If the supply air temperature decreases by 2°F or more within three minutes, the output deactivates, and the test passes. If the supply air temperature does not decrease by at least 2°F within three minutes, the test displays a warning. Other possible results include: Fail - Shut Down Status.

### Power exhaust test

This test is only available if the Damper Test Passes. The damper opens and the exhaust fan output activates. The test passes if you confirm within 10 minutes that the exhaust fan is running. If you do



not confirm this within 10 minutes, the test displays a warning. The test fails if the damper does not open.

## VFD power exhaust test

This test is only available if the Damper Test passes. The damper opens and the exhaust fan VFD ramps from 0% (off) to 100%. If a building static pressure reading is available, the test monitors the pressure during this ramp-up period. The test passes if the building static pressure decreases.

If the building static pressure sensor is not available, you must confirm that the exhaust fan is running. The test passes if you confirm within 10 minutes that the exhaust fan is running. If you do not confirm this within 10 minutes, the test displays a warning. The test fails if the damper does not open.

## ERV pivot test

This test activates the ERV, and prompts you to continue. If you continue and then confirm that the ERV is pivoted, the test passes. If you do not respond within 10 minutes to either of the prompt messages, or you do not confirm that the ERV is pivoted, the test fails.

## Output states after the equipment test

The following table shows the expected output states of the self test.

**Table 17: Output States During the Self-Test**

| Test/Output        | Y1  | Y2  | Exhaust Fan | ERV | Damper                   | Alarm |
|--------------------|-----|-----|-------------|-----|--------------------------|-------|
| Alarm              | Off | Off | Off         | Off | 0%                       | On    |
| Compressor 1       | On  | Off | Off         | Off | 0%                       | Off   |
| Compressor 2       | Off | On  | Off         | Off | 0%                       | Off   |
| Power Exhaust Test | Off | Off | On/Ramp     | Off | 0%                       | Off   |
| ERV Pivot Test     | Off | Off | Off         | On  | 0%                       | Off   |
| Damper Test        | Off | Off | Off         | Off | Ramp Open;<br>Ramp Close | Off   |

## Acceptance test

The Acceptance tests are available when the Damper Test passes. The acceptance test certifies the California Energy Code Title 24 compliance for retrofit units.

## Outdoor air ventilation test

The outdoor air ventilation test certifies compliance with NA7.5.1.2 Outdoor Air Acceptance (Form CEC-MECH-2A). This test disables the economizer and DCV, which causes the damper to open to the fixed minimum position. You measure the OA flow and have 10 minutes to respond to the prompt. Possible results include: Fail - OA flow not measured or Pass.

## Rooftop unit test

The rooftop unit test evaluates the entire thermostat, economizer, and RTU system and certifies compliance with NA7.5.2 Rooftop Acceptance (Form NRCA-MCH-03-A). This test disables the economizer and DCV operation. You have 20 minutes to perform system tests and respond to a prompt on the controller. Possible results include: Fail - RTU prompt not acknowledged, and Pass.

## Economizer test

The economizer test certifies compliance with NA7.5.4 Air Economizer Controls Acceptance (Form NRCA-MCH-05-A). This test disables the DCV and simulates the demand for cooling, free cooling availability, and supply air temperature to quickly open the damper to 100% (Steps 2a and 2b on the form). You must confirm the return air damper operates properly. Another simulation begins to verify integrated economizer operation (Step 2c on the form). The economizer disables and the damper closes to the minimum position (Step 3 on the form). Possible results include: Fail - OA damper not modulating, Fail - RA damper not modulating, Fail - No integrated economizer operation, Fail - Prompt respond not received, and Pass.

## DCV test

The DCV test certifies compliance with NA7.5.5 Demand Control Ventilation Systems Acceptance (Form CEC-MECH-6A). The economizer operation disables and an IAQ sensor reading greater than the active setpoint is simulated. The test verifies that the damper opens from the minimum position (Step 1 on the form). After a one-minute delay, an IAQ sensor reading of 0 ppm simulates and the test system verifies that the damper closes to minimum position (Step 2 on the form). Possible results include: Fail - DCV not functioning, and Pass.

## FDD test

The FDD test certifies compliance with NA7.5.11 Fault Detection and Diagnostics (FDD) (Form NRCA-MCH-12-A). The system instructs you to disconnect the OA temperature sensor from the unit (Step 2 on the form). You must confirm that a fault is reported. After that, you are instructed to reconnect the OA Temperature sensor (Step 3 on the form) and confirm that the faults are cleared. Possible results include: Fail - Faults not detected, Fail - Faults not cleared, and Pass.