PROVENT P/N Α **EST. WEIGHT** SEISMIC CLIP KIT P/N **KNOCK-DOWN ROOF CURBS FOR YORK UNITS FEATURES CBKDSUN367208** 8" 67 Lbs. ZR, XN, XP, WN 036-060 ZE, ZF, KE 036-072 11" 79 Lbs. **CBKDSUN367211** KDKITSUN3672 Roof curb perimeter made of 14" 91 Lbs. galvanized steel. **CBKDSUN367214 CBKDSUN367224** 24" 132 Lbs. Gasketing package provided. When conforming to CBC 2022 and IBC 2021, Heat treated wood nailer provided. include optional seismic Corner flanges are pre- threated for easy bolt on assembly. hold down clip kit. Available on 8"- 14" Pitched, adjustable pitch/ adjustable height, welded, different height, Isolation and calculated curbs are available. **NOTES** 72 1/2" 69" 19 1/2" Attach ductwork to roof curb. Flanges of duct rest on top of curb. Support ductwork below the curb. 1 3/4" Typ. S/A 19 1/2" R/A Wood Nailer 1 3/4" Pre-threated 1/4"- 20 x 3/4" Bolt Flange⁻ **CORNER DETAIL CROSS SECTION DETAIL** 3847 WABASH DR. SUBMITED TO: FORM NO: **PART NUMBER: ProVent** MIRA LOMA, CA 91752 **CBKD-102** CBKDSUN3672 SERIES

COMPANY: _

JOB NAME: _

NOTES:

EQUIPMENT:

DATE:

1/7/2025

REV:

5

DRAWN BY:

CNG

PHONE (951) 685-1101

FAX (619) 872-9799